www.Inspection-for-Industry.com

Document Name:

• Contractor Quality Control Plan for Storage Tank Erection

		Re	Responsibility		
No.	Item description	СС	TPI	Owner	
3.6	Atmospheric storage tanks				
3.6.1	Pre-installation check				
	1) Foundation				
	- Dimensional check before tank				
	erection				
	- Level Icheck under tank shell	Н			
	- Diameter, direction and slope				
	- Location and dimension of drain sump				
	pit				
	- Visual				
	2) Welding test				
	- Welding prodecure test	Н			
	- Procedure qualification test				
	- Welder performance qualification				
0.00	tests				
3.6.2	Erection 4) Worlding in an action				
	1) Welding inspection				
	- Visual inspection (Welding & PWHT)				
	Bottom plates Vacuum test				
	- Radiographic examination of butt				
	joints for annular under shell plates				
	3) Shell plates				
	- Hydrostatic test				
	- Radiographic examination				
	- Liquid penetrant examination of	н			
	welding seams, if specified				
	- MagneTPI parTPIle examination, if				
	specified				
	- Level and out of plumbness				
	4) Roof plates				
	- Vacuum test				
	- Air test for roof plate & pontoon				
	compartments				

www.Inspection-for-Industry.com

Document Name:

• Contractor Quality Control Plan for Storage Tank Erection

.....

fr .				1
	-	Oil penetration or vacuum test for		
		deck plate and pontoon		
	5)	Appurtenance		
	-	Orientation and dimensional check		
	-	Liquid penetrant examination of shell		
		nozzle and reinforcing plate		
	-	Air test of shell nozzle reinforcing		
		plate		
	-	Hydrotest for heating unit		
	-	Air test of roof drain pipe for floating		
		roof tank		
	-	Visual check		
3.6.3	Final cl	neck after erection		
	1)	Hydrostatic test (Tank fill & held for 24		
		hours)		
	2)	Final inspection		
	3)	Visual check	Н	
	-	Plumbness checks		
	-	Roundness checks		
	-	Peaking checks		
	-	Banding checks		

CC: Construction Contractor

TPI: Third Party Inspection

H: Hold Point; Hold on the production till TPI Inspector performs inspection and supervise the required test